...e Health Post Building (Two Type...

नेपाल सरकार

पूर्वाधार विकास मन्त्रालय

शहरी विकास तथा भवन निर्माण विभाग

संघीय शहरी विकास तथा भवन निर्माण कार्यालय, बबरमहल, काठमाडौं

नेपाल सरकार
पूर्वाधार विकास मन्त्रालय
शहरी विकास तथा भवन निर्माण विभाग
संघीय शहरी विकास तथा भवन निर्माण कार्यालय
बबरमहल, काठमाडौं

बोलपत्र संशोधनको सुचना

सुचना प्रकाशित मितिः २०८३/०६/२३

The Following changes are made in the Bid Document

SN	Relevant Clause No/Name	Existing Clause(Unit)	Modified Clause(Unit)	Remarks
1	BOQ Item no 13 -Well seasoned salwood chaukhats for fixed/openable door/windows with good finish of approved quality incuding fixing in postion with necessary M.S. hold fasts on new or existing damage opening all complete as per instruction of site Engineer.	Cum	Sqm	BOQ attached

Scanned with CamScanner

S.N.	Description of works	Units	Quantity	Rate	Rate in Words	Amount	Remarks
9	Colouring with 2 coats of weather coat of approved colour with 1 coat of primer Painting over porperly cleaned surface all complete as per instruction of site engineer.	Sqm.	441.18				
10	Colouring with two coats of ready made enamel paint with over one coat of primer Painting over properly sanded surface all complete as per instructon of site Engineer.	Sqm.	157.10				
11	Supplying and fitting Ready made Teak wood Doors,ordinary (Seasoned and Poisoned treated ,one side teak) with all neccessary hardware all complete as per instruction of site Engineer	Sqm	3.80				
12	Supplying and fitting Ready made Teak wood Doors,ordinary (Seasoned and Poisoned treated ,one side teak and other side water proof ply fitting) with all neccessary hardware all complete as per instruction of site Engineer	Sqm	5.95				
13	Well seasoned salwood chaukhats for fixed/openable door/windows with good finish of approved quality incuding fixing in postion with necessary M.S. hold fasts on new or existing damage opening all complete as per instruction of site Engineer.	Cu m	0.24				
14	0.45 mm Plain GI sheet on door with proper shape & size, all necessary nails, screws, bolts, nuts washers, fevicol etc as per drawing & instruction all complete.	Sqm.	5.95				
15	Supply and fixing of M.S. collapsible gate including with primer painting and all necessary accessories all complete as per instructions	Sqm.	6.96				
16	Supply and fixing of M.S. grill with two coat redoxide paint all complete works as per specifications and instructions	Kgs	200.00				
17	Fixing of 5 mm thick glass on existing fixed frames of windows, ventilators with or without wooden beading & putty all complete as per instruction of site Engineer.	Sqm.	15.21				
18	12.5mm thick cement sand plaster in (1:4) ratio on floor/wall of good finish including racking the joint, wetting of surfaces & curing including scaffolding work all complete as per instruction of site Engineer.	Sqm.	167.42				

Scanned with CamScanner