



Government of Madhesh Province
Ministry of Physical Infrastructure Development
Infrastructure Development Directorate
Provincial and Local Roads Improvement Program (PLRIP)
Provincial Project Management Unit (PPMU)
Janakpurdham, Dhanusha, Nepal

Bid Addendum Report
Addendum No. 1 (One)

Date of Publication (Addendum No. 1): October 1, 2026

International Competitive Bidding
(Two-envelope with Rated Criteria)

Contract title: Upgrading/Construction works of Kalaiya-Malahi Road (16.226Km) of Bara District

Issued on: *August 20, 2026*

Invitation for Bids No.: 01-PPMU/PLRIP/083-84

ICB No.: 01

Contract Identification No.: PLRIP/M/BARA/W/ICB/UG/01/083-84

Government of Madhesh Province
Ministry of Physical Infrastructure Development
Infrastructure Development Directorate
Provincial and Local Roads Improvement Program (PLRIP)
Provincial Project Management Unit (PPMU)
Janakpurdham, Dhanusha, Nepal

Clarifications on the queries from the prospective bidders

Clarification No. 1 (One)

This is to notify that the Provincial and Local Roads Improvement Program (PLRIP), Provincial Project Management Unit (PPMU), Janakpurdham, Dhanusha, Nepal has issued following clarifications on the queries from the prospective Bidders on the Bidding Documents regarding invitation for bids published in Gorkhapatra daily newspaper on 20th August 2026 for the Procurement of **Upgrading works of Kalaiya-Malahi Road (16.226Km) of Bara District**, Request for Bids (RFB) No: PLRIP/M/BARA/W/ICB/UG/01/083-84

Sl.No	Bidding Document Reference					Bidders's Questions	Clarifications
	Chapter/ Section.	Heading	Subject/ title	Page No	Line No		
1	Request for Bids	S.N 9		iii		Can bidder's submit the bid security of amount NPR 30,800,000.00, équivalent to USD. ?	The bidders shall submit the "Bid Security" of US\$ 200,000.00 or NPR 30,800,000.00 as per notice.
2	Section I	Instructions to Bidders	A. General	7 to 38		Placing of Sub Clause No. needs to be adjusted.	Placing of Sub Clause No. from 1.1 to 50.1 is

Sl.No	Bidding Document Reference					Bidders's Questions	Clarifications
	Chapter/ Section.	Heading	Subject/ title	Page No	Line No		
							to be adjusted from page 7 to page 38 accordingly.
3	Section II	Bid Data Sheet (BDS)	ITB 11.6	41		Can the Lead Member issue a Power of Attorney on its letterhead authorizing another JV member to sign and submit the bid on behalf of the JV?	The Power of Attorney must be given to the authorized representative of the lead member of the JV.
4	Section II	Bid Data Sheet (BDS)	ITB 19.3 (a)	43		Can use bank's use own format for bid security?	Bid Security shall be in the form of an unconditional and irrevocable guarantee issued by a bank as per the form provided in Section IV Bidding, Forms, Form of Bid Security – Demand Guarantee.
5	Section II	Bid Data Sheet (BDS)	ITB 21.1	44		What happens if a bid is sent by courier prior to bid submission date but it is not received in Office due to delays of courier?	Bidder shall have the option of submitting their Bids by courier. But Bids must be delivered and submitted in office before the submission deadline as per ITB 22.1 Late bids will be rejected.
6	Section II	Bid Data Sheet (BDS)	ITB 32.2	45		How bid can be evaluated as per the Rated Criteria? And	The Weightage of technical factor will be divided into sub factors

Sl.No	Bidding Document Reference					Bidders's Questions	Clarifications
	Chapter/ Section.	Heading	Subject/ title	Page No	Line No		
						How can you breakdown the weightage of technical factor?	and shall be added in Addendum No:1
7	Section II	Bid Data Sheet (BDS)	ITB 36.1	47		If One bidder submits their bid in NPR and other bidder will submit their Bid in US\$, how can you compare the financial bid?	Bids shall be expressed entirely in local currency i.e. NPR. Foreign currency portion expressed in Table C of the Table of Adjustment Data of the bid shall be evaluated/ adjusted in accordance with ITB 36.1.
8	Section II	Bid Data Sheet (BDS)	J, ITB 32.2 & ITB 40.1	47		How the combined Evaluation of Technical and Financial Parts will be done?	The Bid evaluation process is given in Section III - Evaluation and Qualification Criteria (Without Prequalification)
9	Section III	Evaluation and Qualification Criteria (Without Prequalification)	Evaluation of Technical Proposal	58		How can you give the technical score of Technical Proposal	The table for technical proposal scoring methodology is provided in Section III

Sl.No	Bidding Document Reference					Bidders's Questions	Clarifications
	Chapter/ Section.	Heading	Subject/ title	Page No	Line No		
10	Section III	EQC 3.2	Average Annual Construction Turnover	65		As per the World Bank Standard Bidding Document (SBD), the usual requirement is an average annual construction turnover for 3/3 years. Price Index of NRB is considered or not?	Monetary amounts required in Section III- Evaluation and Qualification shall be indicated by the Bidders in USD equivalent using the exchange rates in accordance with the initial paragraphs of Section III. Price Index of NRB is not applicable.
11	Section III	EQC 4.1 (a)	General Construction Experience	66		Experience under construction contracts in the role of prime contractor, JV member, Subcontractor, or management contractor for at least the last 10 years, starting 1st January, 2016, Why?	As per EQC 4.1 (a) , The firm shall have a total general work experience of 10 years, starting 1st January, 2016.
12	Section III	EQC 4.2 (a)	Specific Construction & Contract Management Experience	66		Regarding the 4.2 (a), 1 (One) Bituminous Road contract, of minimum value of; USD \$ 8 million has required, can apply the Price Index of NRB in this value?	Only the Bidder's share, by value, shall be considered and Price Index of NRB will not be applied.
13	Section III	EQC 4.2 (c)	Specific Experience in managing ES aspects	68		Regarding the SN 4.2 (c), Specific Experience in managing ES aspects, Bid Documents state as follows "Developed and implemented (50% of Works) and/or completed ESMP (C-ESMP) on road construction/	At least 50% of the value of Works contract (with value USD 3.32 Million or more) should be completed in which the specified ES aspects are part of the

Sl.No	Bidding Document Reference					Bidders's Questions	Clarifications
	Chapter/ Section.	Heading	Subject/ title	Page No	Line No		
						improvement contracts of contract value USD 3.32 million or more. Queries: What is the meaning of 50% of works? Does it mean the value should be 50% of the CESMP which is developed and implemented? Please clarify. Is it feasible for bid when only the bidder's share, by value, and role and responsibilities shall be considered?	contract to comply with the requirements. The bidder's share, by value, and role and responsibilities shall be considered for above contract.
14		ITB 22.1	Extension of Time			We kindly request an extension of time for the preparation of our bidding documents due to the complexity of the project.	The time for submission of the bid has been amended. Please refer to the Addendum No. 1.
15	Section IV Bill of Quantities	Original BOQ ,Pay Item No. 1.1	Site Clearance	150		Is quantity for clearing and grubbing road land 38942.40 Square meter is sufficient?	The quantity has been corrected and amended. Please refer to the Addendum No. 1.
16	Section IV Bill of Quantities	Original BOQ ,Pay Item No. 3.1	Pavement layers	153		Is quality for Scarifying the existing road surface 58,413.60 Cubic meter correct ?	The quantity has corrected and amended. Please refer to the Addendum No. 1

Sl.No	Bidding Document Reference					Bidders's Questions	Clarifications
	Chapter/ Section.	Heading	Subject/ title	Page No	Line No		
17	Section VII – Works’ Requirements	Drawings		230		Could you please provide the CAD copy of drawings provided with the Bid?	The drawing (in PDF format) is uploaded on the website: ppmu.madhesh.gov.np in download section.
18	Section IX	Particular Conditions Part A	Sub- Clause 2.1 Time for access to the Site	237		As per Particular Conditions, Sub-Clause 2.1, possession of the Site shall be handed over in two installments, 70% and 30%. The 70% of the Site will be available at the Commencement Date, and the remaining 30% within three (3) months thereafter. Kindly clarify which specific sections of the Site will be made available at the Commencement	The whole section of the site will be made available at commencement date, however, there are certain unidentified sections (not exceeding 30% of the total) which may not be available to immediately start work. These sites will be made available within 3 months from the commencement date.
19	Section IX	Particular Conditions Part A	Sub-Clause 4.2 Performance Security	237		The clause requires a Performance Security of 8 % of the Accepted Contract. i. 6% of the Accepted Contract Amount having validity period up to the completion of Defect Notification Period of Phase 1 (Upgradation/Construction Work) plus 28 days ii. 2% of the Accepted Contract Amount having	Performance Securities for both phases shall be submitted together.

Sl.No	Bidding Document Reference					Bidders's Questions	Clarifications
	Chapter/ Section.	Heading	Subject/ title	Page No	Line No		
						validity period up to issue of the Performance Certificate of Phase 2 plus 28 days. Query: Could the Employer accept 2% Performance Security for Phase 2, commencing from the Commencement Date of Phase 2?	
20	Section IX	Particular Conditions Part A	Sub-Clause 21.1 List of proposed members of DAAB	237		Are DAAB members required at the time of tender, or can they be proposed after contract award? What are the requirements for DAAB personnel composition?	The Bidder shall furnish in the Letter of Bid-Technical Part the names of three potential DAAB members and attach their curriculum vitae. The requirements for DAAB personnel composition are prescribed in “3. Warranties” under “Appendix- General Conditions of DAAB Agreement” of Part B - Special Provisions of Request of Bids (RFB) document.

Government of Madhesh Province
Ministry of Physical Infrastructure Development
Infrastructure Development Directorate
Provincial and Local Roads Improvement Program (PLRIP)
Provincial Project Management Unit (PPMU)
Janakpurdham, Dhanusha, Nepal

Addendum Notice No. 1(one)

This is to notify that the Provincial and Local Roads Improvement Program (PLRIP), Provincial Project Management Unit (PPMU), Janakpurdham, Dhanusha, Nepal has made the following amendments to the bidding document relating with the Invitation for Bids published in Gorkhapatra daily newspaper on 20th August 2026 for the Procurement of **Upgrading works of Kalaiya-Malahi Road (16.226Km) of Bara District, Request for Bids (RFB) No. :PLRIP/M/BARA/W/ICB/UG/01/083-84** has been amended as per the provision of the ITB-8 of the bidding document as follows. All other terms and conditions will remain unchanged.

Sl. No	Bidding Document Reference					Original Provision	Modified Provision
	Chapter/Section.	Heading	Subject/title	Page No	Line No		
1	Invitation for Bids	Request for Bids Works	1	ii		1. <i>The Government of Nepal [GoN] has received financing from the World Bank toward the cost of the Provincial and Local Roads Improvement Program (PLRIP) and intends to apply part of the proceeds toward payments under</i>	1 The Government of Nepal [GoN] has received financing from the World Bank toward the cost of the Provincial and Local Roads Improvement Program (PLRIP) and intends to apply part of the proceeds toward payments under the contract for Upgrading works of

Sl. No	Bidding Document Reference					Original Provision	Modified Provision
	Chapter/Section.	Heading	Subject/title	Page No	Line No		
						the contract for Upgrading works of <i>Kalaiya-Malahi Road (16.226Km) of Bara District.</i> For this contract the Borrower shall process the payments using the Direct Payment disbursement method, as defined in the World Bank's Disbursement Guidelines for Investment Project Financing.	Kalaiya-Malahi Road (16.226Km) of Bara District.
2	Invitation for Bids	Request for Bids Works	1	iii		7. Bids, both Technical and Financial must be submitted in hard copy, at the address below by hand/courier on or before 12:00 hours (Nepal Standard Time) on October 6, 2026. The outer Bid envelopes marked "ORIGINAL BID", and the inner envelopes marked "TECHNICAL PART" will be publicly opened in the presence of the Bidders' designated representatives and anyone who chooses to attend, at the address below on Project Management Unit (PPMU), Janakpur, Dhanusha, 13:00 hours (Nepal Standard Time) on October 6, 2026. All envelopes marked	7. Bids, both Technical and Financial must be submitted in hard copy, at the address below by hand/courier on or before 12:00 hours (Nepal Standard Time) on October 15, 2026 . The outer Bid envelopes marked "ORIGINAL BID", and the inner envelopes marked "TECHNICAL PART" will be publicly opened in the presence of the Bidders' designated representatives and anyone who chooses to attend, at the address below on Project Management Unit (PPMU), Janakpur, Dhanusha, 13:00 hours (Nepal Standard Time) on October 15, 2026 . All envelopes marked "FINANCIAL PART" shall

Handwritten signature/initials

Sl. No	Bidding Document Reference					Original Provision	Modified Provision
	Chapter/Section.	Heading	Subject/title	Page No	Line No		
						“FINANCIAL PART” shall remain unopened and will be held in safe custody of the Employer until the second public Bid opening.	remain unopened and will be held in safe custody of the Employer until the second public Bid opening.
3	Invitation for Bids	Request for Bids Works	1	iii		8. Late Bids will be rejected. The “TECHNICAL PART” of the bid will be publicly opened in the presence of the Bidders’ designated representatives and anyone who chooses to attend, at the address below immediately after bid submission deadline on October 6, 2026. at 13:00 hrs. “FINANCIAL PART” of the bid shall remain unopened until the second public Bid opening, notified after completion of evaluation of Technical Part of the bid.	8. Late Bids will be rejected. The “TECHNICAL PART” of the bid will be publicly opened in the presence of the Bidders’ designated representatives and anyone who chooses to attend, at the address below immediately after bid submission deadline on October 15, 2026 , at 13:00 hrs. “FINANCIAL PART” of the bid shall remain unopened until the second public Bid opening, notified after completion of evaluation of Technical Part of the bid.
4	Section II	Bid Data Sheet (BDS)	ITB 22.1	44		For Bid submission purposes only, the Employer’s address is: Attention: Provincial and Local Roads Improvement Program (PLRIP) Provincial Project Management Unit (PPMU) Street Address: Madhesh Province, Janakpurdham, Dhanusha City: Janakpurdham Country: Nepal.	For Bid submission purposes only, the Employer’s address is: Attention: Provincial and Local Roads Improvement Program (PLRIP) Provincial Project Management Unit (PPMU) Street Address: Madhesh Province, Janakpurdham, Dhanusha City: Janakpurdham Country: Nepal. The deadline for Bid submission is:

Sl. No	Bidding Document Reference					Original Provision	Modified Provision				
	Chapter/Section.	Heading	Subject/ title	Page No	Line No						
						The deadline for Bid submission is: Date: October 6, 2026 Time: 12:00 hours (Nepal Standard Time)	Date: October 15, 2026 Time: 12:00 hours (Nepal Standard Time)				
5.	Section II	Bid Data Sheet (BDS)	ITB 25.1	44		The Bid opening shall take place at: Provincial and Local Roads Improvement Program (PLRIP) Provincial Project Management Unit (PPMU), Janakpur, Dhanusha City: Janakpur, Dhanusha Country: Nepal Date: October 6, 2026 Time: 13:00 hours (Nepal Standard Time)	The Bid opening shall take place at: Provincial and Local Roads Improvement Program (PLRIP) Provincial Project Management Unit (PPMU), Janakpur, Dhanusha City: Janakpur, Dhanusha Country: Nepal Date: October 15, 2026 Time: 13:00 hours (Nepal Standard Time)				
6	Section II	Bid Data Sheet (BDS)	ITB 32.2	45		<table><tr><td>Technical Factor</td><td>weight in percentage (insert weight in %)</td></tr></table>	Technical Factor	weight in percentage (insert weight in %)	<table><tr><td>Technical Factor</td><td>weight in percentage (insert weight in %)</td></tr></table>	Technical Factor	weight in percentage (insert weight in %)
Technical Factor	weight in percentage (insert weight in %)										
Technical Factor	weight in percentage (insert weight in %)										

Sl. No	Bidding Document Reference					Original Provision		Modified Provision									
	Chapter/Section.	Heading	Subject/ title	Page No	Line No												
						1. Construction Methodology: Description of construction methodology/ technology / innovation for key construction activities including methodology to address the risks and challenges identified at site/sustainability (Earthworks, Retaining Structures, Bridges, Drainage/Cross Drainage Works, and Pavement Works (flexible/rigid) including Sub-grade, Sub-base, WMM, DBM & BC, Geotechnical investigations, various stages of Bridge Construction etc.), Road Safety and 5 year Post Construction Maintenance.	40		<table><tr><td>1. Construction Methodology:</td><td>40 %</td></tr><tr><td>1(a) Description of existing site condition of road, utilities, drainage, etc. with photographs and Identification of risks and challenges in construction including traffic management and safety, and mitigation measure to be applied during construction.</td><td>10%</td></tr><tr><td>1(b) Description of construction methodology/ technology/ innovation for key construction activities (Earthworks, Retaining Structures, Drainage Works, and Pavement Works) addressing the identified risks and challenges</td><td>20%</td></tr><tr><td>1(c) Operation and Maintenance of existing road during construction/ improvement for smooth traffic flow without hinderance</td><td>10%</td></tr></table>	1. Construction Methodology:	40 %	1(a) Description of existing site condition of road, utilities, drainage, etc. with photographs and Identification of risks and challenges in construction including traffic management and safety, and mitigation measure to be applied during construction.	10%	1(b) Description of construction methodology/ technology/ innovation for key construction activities (Earthworks, Retaining Structures, Drainage Works, and Pavement Works) addressing the identified risks and challenges	20%	1(c) Operation and Maintenance of existing road during construction/ improvement for smooth traffic flow without hinderance	10%
1. Construction Methodology:	40 %																
1(a) Description of existing site condition of road, utilities, drainage, etc. with photographs and Identification of risks and challenges in construction including traffic management and safety, and mitigation measure to be applied during construction.	10%																
1(b) Description of construction methodology/ technology/ innovation for key construction activities (Earthworks, Retaining Structures, Drainage Works, and Pavement Works) addressing the identified risks and challenges	20%																
1(c) Operation and Maintenance of existing road during construction/ improvement for smooth traffic flow without hinderance	10%																

Sl. No	Bidding Document Reference					Original Provision	Modified Provision
	Chapter/Section.	Heading	Subject/title	Page No	Line No		
						2. Quality Assurance Plan and Procedures: Detail description of methodology for Quality Assurance and procedure (Material, Quarry Site, Processing and Testing, Storing, Transportation, Laying, etc.) including Survey and Setting out, maintaining line and level for each construction activity. 15	2. Quality Assurance Plan and Procedures: 2(a) Details description of methodology for Quality Assurance plan and procedure (Material, Quarry Site, Processing and Testing, Storing, Transportation, Laying, Testing, etc. 10% 2(b) Survey and setting out, maintaining line and level for each construction activity 5%
						3. Work Schedule and Resource Planning: (a) Work Schedule: Detail description of work schedule that is realistic with identification of critical path activities, sequencing order of carrying out the works including the timing of each stage, resource 25	3. Work Schedule and Resource Planning: 3 (a) Work Schedule: Detail description of work schedule that is realistic with identification of critical path activities, sequencing order of carrying out the works including the timing of each stage, resource deployment, etc. to accomplish the task within allocated time frame. The 15%

Sl. No	Bidding Document Reference					Original Provision	Modified Provision
	Chapter/Section.	Heading	Subject/title	Page No	Line No		
						deployment, etc. to accomplish the task within allocated time frame. The Programming software proposed will also be evaluated. (as a minimum it is expected the critical path of the project is detailed with approximate time scales for each activity) (b) Resource Planning: Overall resource planning (Human resource/Key personnel, Materials Resources and Plant and Equipment Resources available for the phase 1 and phase 2 of the contract) in sequential order of all activities described in above heading presented in Network Diagram/ Critical Path Method.	Programming software proposed will also be evaluated. (as a minimum it is expected the critical path of the project is detailed with approximate time scales for each activity)
							3.(b) Resource Planning: Overall resource planning (Human resource/Key personnel, Materials Resources and Plant and Equipment Resources available for the phase 1 and phase 2 of the contract) in sequential order of all activities described in above heading presented in Network Diagram/ Critical Path Method.
							10%

Sl. No	Bidding Document Reference					Original Provision	Modified Provision
	Chapter/Section.	Heading	Subject/title	Page No	Line No		
						4. Management strategies and implementation plans (MSIPs) for Environmental and Social Management: This should include: a. General: organizational structure, quality of proposed E&S team, monitoring, reporting and assurance; b. Environment: key risks and mitigation measures including (but not limited to) dust, noise, erosion and sedimentation control, water management (including pollution prevention), materials sourcing, waste management (including spoil), WASH provisions, etc.; c. Social: Methodology and approach for managing social risks, including	10%

Sl. No	Bidding Document Reference					Original Provision	Modified Provision
	Chapter/Section.	Heading	Subject/title	Page No	Line No		
						labour recruitment and working conditions, employing more female workers, influx management, prevention of child/forced labour, GBV (SEA/SH) prevention and response, stakeholder engagement, grievance redress. Etc.	
						5. MSIPs regarding Occupational and Community Health and Safety (OHS/CHS): This should include, as a minimum: a. Company health and safety policies and procedures and organizational structure; b. Code of conduct; c. Overview of OHS/CHS risks, impacts, and mitigation measures with a focus on high hazard activities, equipment provision (such	5. MSIPs regarding Occupational and Community Health and Safety (OHS/CHS): This should include, as a minimum: a. Company health and safety policies and procedures and organizational structure; b. Code of conduct; c. Overview of OHS/CHS risks, impacts, and mitigation measures with a focus on high hazard activities, equipment provision (such as barrier types, PPE, etc.), diversions; d. Emergency response (including first aid and fire protection provisions at camps, office, and work areas); e. labor camp management standards
						10	10%

Sl. No	Bidding Document Reference					Original Provision		Modified Provision	
	Chapter/Section.	Heading	Subject/title	Page No	Line No				
						as barrier types, PPE, etc.), diversions; d. Emergency response (including first aid and fire protection provisions at camps, office, and work areas); e. labor camp management standards for all categories of workers, workers' GRM, health, safety, and security measures for project-affected communities (e.g., noise, dust, traffic, communicable diseases, etc.).		for all categories of workers, workers' GRM, health, safety, and security measures for project-affected communities (e.g., noise, dust, traffic, communicable diseases, etc.).	
						Total	100	Total	100
						Minimum Technical Score to Pass (to qualify for opening of Financial Part of the Bid): 50 %		Minimum Technical Score to Pass (to qualify for opening of Financial Part of the Bid): 50 %	
7	Section III	Evaluation and Qualification Criteria	Evaluation of Bids	Key Personnel listed 55		1. Contractor's Representative		1. Contractor's Representative (Team Leader)	
						3. Pavement Engineer		Removed	
						4. Structural/Geotechnical/Bridge Engineer		4. Geotechnical	

Sl. No	Bidding Document Reference					Original Provision	Modified Provision
	Chapter/Section.	Heading	Subject/title	Page No	Line No		
8	Section IV -	Bidding Forms	Form PER -1: Contractor's Representative and Key Personnel Schedule	90		1. Contractor's Representative	1. Contractor's Representative (Team Leader)
						3. Pavement Engineer	Removed
						4. Structural/Geotechnical/ Bridge Engineer	4. Geotechnical
9	Section V	Bill of Quantities	Pay Item No. 1.1	150		Clearing and grubbing road land of all categories including removal of anthills, uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned, up to a lead to Environmentally Safe Tipping Site including removal and disposal of top organic soil [Spec Cl no. 201]. Unit : Square meter Quantity : 38,942.40	Clearing and grubbing road land of all categories including removal of anthills, uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned, up to a lead to Environmentally Safe Tipping Site including removal and disposal of top organic soil [Spec Cl no. 201]. Unit : Square meter Quantity : 74,620.96

Sl. No	Bidding Document Reference					Original Provision	Modified Provision
	Chapter/Section.	Heading	Subject/title	Page No	Line No		
10	Section V	Bill of Quantities	Pay Item No. 3.1	153		Scarifying the existing road surface as instructed by the Engineer, disposal of unsuitable scarified material for all lifts and lead. [Spec Cl no. 1003]. Unit : Cubic meter Quantity : 58,413.60	Scarifying the existing road surface as instructed by the Engineer, disposal of unsuitable scarified material for all lifts and lead. [Spec Cl no. 1003]. Unit : Cubic meter Quantity : 12,169.50
11	Section VII	Works' Requirements	Contractor's Representative and Key Personnel	229		1. Contractor's Representative	1. Contractor's Representative (Team Leader)
						3. Pavement Engineer	Removed
						4. Structural/Geotechnical/Bridge Engineer	4. Geotechnical

Chapter: Bill of Quantities



Madhesh Province Government
Ministry of Physical Infrastructure Development
Infrastructure Development Directorate
Provincial and Local Road Improvement Program (PLRIP)
Provincial Project Management Unit (PPMU)
Janakpurdham, Dhanusha, Nepal

BILL OF QUANTITIES (As per Addendum No. 1)

Name of the Road : Kalaiya -Malahi Road, Bara District

Chainage : 0+000 To 16+226

S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
	1		Site Clearance					
1	1.1	DOR-201	Clearing and grubbing road land of all categories including removal of anthills, uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned, up to a lead to Environmental Safe Tipping Site including removal and disposal of top organic soil [Spec Cl no. 201].	Square meter	74,620.96			
2	1.2		Cutting of trees, including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable material with all lifts, lead and earth filling in the depression/pit. Tree girths as follows: [Spec Cl no 201]:					
	a	DOR-201	from 300 mm to 600 mm	Number	39.00			

K. andraf.

S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
	b	DOR-201	above 600 mm to 900 mm	Number	16.00			
	c	DOR-201	above 900 mm to 1800 mm	Number	19.00			
3	1.3		Dismantling of existing culverts, bridges, retaining walls and other structure; including use of scaffolding wherever necessary and for any lifts; sorting of the dismantled material, disposal of unserviceable material to environmentally safe tipping site and stacking of serviceable material. The dismantled structures comprising of the following: [Spec Cl no. 202]:					
	a	DOR-202	Brickwork	Cubic meter	544.90			
	d	DOR-202	Plain and reinforced cement concrete	Cubic meter	167.89			
	1	DOR-202	RCC pipe over 600 mm and up to 900 mm	meter	135.00			
			Sub-total of Site Clearance					
	2		Earthworks					-
4	2.1	DOR-905, 906	Roadway excavation by mechanical means in all types of soil and hard rock, as per Drawings and instruction of the Engineer for all lift and lead up to safe environmental tipping site including removal of stumps and other deleterious matter. [Spec Cl no.905, 906].	Cubic meter	3,161.03			
5	2.2	DOR-907	Excavation for foundation by mechanical means in all types of soil and hard rock, including shoring as per Drawings, removal of stumps and other deleterious matter, dewatering and instruction of the Engineer: for all lifts and disposal lead up to Safe Environmental tipping site. [Spec Cl no. 907].	Cubic meter	16,838.63			


S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
6	2.6	DOR-909, 910	Providing, laying, spreading and compacting embankment with approved material as instructed by the Engineer and including cost of transportation. [Spec Cl no. 909, 910].	Cubic meter	194,255.10			
7	2.7	DOR-3110	Providing and filling with filter media composed of riverbed granular material or stone crushed aggregates to a thickness as per Drawings or as instructed by the Engineer, with smaller size towards the soil, behind retaining or other structures and compacted to a firm condition. [Spec Cl no. 3110].	Cubic meter	119.64			
8	2.8	DOR-908	Providing and filling with suitable local material to a thickness as per Drawings or as instructed by the Engineer, behind retaining or other structures and compacted as per specification [Spec Cl no. 908].	Cubic meter	3,720.36			
9	2.9	DOR-1707	Providing and filling with sand to a thickness as per Drawings or as instructed by the Engineer, behind retaining or other structures and compacted as per specification. [Spec Cl no. 1707].	Cubic meter	48.04			
10	2.1	DOR-627, 2403,2404	Providing and laying of geotextile in subsurface drain, road embankment, behind structures, as per Drawings or as instructed by the Engineer. [Spec Cl no 627, 2404].	Square meter	4,529.91			
			Sub-total of Earthworks					
	3.0		Pavement layers					
11	3.1	DOR-1003	Scarifying the existing road surface as instructed by the Engineer, disposal of unsuitable scarified material for all lifts and lead. [Spec Cl no. 1003].	Cubic meter	12,169.50			
12	3.2	DOR-1003, 1005	Preparation of subgrade by cutting or filling up to a depth of 500 mm to designed grade, line, level, super-elevation and camber including watering and compaction. [Spec Cl no.1003, 1005].	Square meter	175,666.51			
13	3.4	DOR-3111	Providing and laying of stone soling with 150 to 200 mm thick cobbles, hand packed on prepared surface as per Specifications, Drawings or as instructed by the Engineer. [Spec Cl no. 3111].	Cubic meter	1,283.54			

S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
14	3.5 (a)	DOR-1201	Providing and laying of granular sub-base of Grading as per Standard Specifications, Drawings or as instructed by the Engineer, on prepared surface, mixing at OMC, and compacted to designed grade, line, level, super-elevation and camber.[Spec Cl no 1201].	Cubic meter	44,762.10			
15	3.5 (c)	DOR-905, 1201	Reuse of existing base & subbase as granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density all complete as per Drawing and Technical Specifications [Spec Cl no 905, 1201].	Cubic meter	8,383.15			
16	3.6	DOR-1204	Providing and laying Crusher Run Macadam base-course of Grading as per Standard Specifications, Drawings or as instructed by the Engineer, on prepared surface, spreading and mixing, watering and compacting to designed grade, line, level, super-elevation and camber. [Spec Cl no. 1204].	Cubic meter	18,031.64			
17	3.9	DOR-1302	Providing and applying MC 70 bitumen prime coat at spray rate as per Standard Specifications, Drawings or as instructed by the Engineer, on prepared base-course including cleaning of road surface and spraying by mechanical means and use of sand blinder when required. [Spec Cl no. 1302].	Liter	103,037.96			
18	3.10	DOR-1302	Providing and applying approved viscosity grade bitumen (alternatively RC 70 cutback at sub-zero temperature) for tack coat at spray rate as per Standard Specifications, Drawings or as instructed by the Engineer, including cleaning of road surface and spraying by mechanical means. [Spec Cl no. 1302].	Liter	61,822.78			
19	3.15	DOR-3202	Providing and laying of M30/20 concrete for rigid pavement including preparing the surface, side form work, mechanical vibration, drawing skid-resistant patterns on the surface, barricading and curing as specified in the Special Specifications, Drawings, or as instructed by the Engineer. [Spec Cl no. 3202].	Cubic meter	5,654.62			

K. and h. f.

S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
20	3.16	DOR-3202, 2019	Providing expansion joint made out of dia 32mm MS dowels (500 mm long) a half length seethed in polyethylene pipe, including MS chairs, all complete as specified in the Special Specifications, Drawings, or as instructed by the Engineer [Spec Cl no. 3202, 2019].	Number	33,848.00			
21	3.17	DOR-1309	Providing and laying Bituminous concrete/ Asphalt concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler as per Drawing and Technical Specifications [Spec Cl no. 1309].	Cubic meter	5,151.90			
22	3.18	DOR-1900	Providing and fixing in position 20 mm thick premoulded joint filler board in expansion joint for fixed ends of simply supported spans not exceeding 10 m to cater for a horizontal movement upto 20 mm, covered with joint sealant all complete as per Drawing and Technical Specifications or as instructed by the Engineer [Spec Cl no. 1900].	meter	5,404.00			
23	3.19	DOR-1900	Providing and filling joint sealing compound with coarse sand and 6 per cent bitumen by weight all complete as per Drawing and Technical Specifications or as instructed by the Engineer [Spec Cl no. 1900].	meter	3,194.00			
24	3.2	DOR-1900	Providing and fixing of Separation Membrane of impermeable plastic sheeting 125 micron thick as per Drawing and Technical Specifications.[Spec Cl no. 1900].	Square meter	25,552.00			
			Sub-total of Pavement Layers					
	4.0		Masonry and Gabion Works					
25	4.1		Brick Masonry by providing and laying first-class brick to the required height, batter, and level as per Drawings or as instructed by the Engineer, in flush joint, including dewatering, scaffolding, curing, PVC weep-holes and other incidentals with the following mortar: [Spec Cl no. 2500].					
	b	DOR-2500	cement-sand mix of 7.5 N/sq.mm strength	Cubic meter	124.39			

S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
26	4.2	DOR-2510	Pointing work with 5.0 N/sq.mm strength cement-sand mortar on masonry walls of all heights, batter, and level as per Drawings or as instructed by the Engineer, including dewatering, scaffolding, curing, all complete. [Spec Cl no. 2510].	Square meter	333.75			
27	4.3		Coursed rubble masonry by providing and laying to the required height, batter, and level as per Drawings or as instructed by the Engineer, in flush joint, including dewatering, scaffolding, curing, PVC weep-holes and other incidentals with the following cement-sand mortar mixes [Spec Cl no.2606].					
	b	DOR-2606	cement-sand mix of 7.5 N/sq.mm strength	Cubic meter	5,273.30			
28	4.6	DOR-2402	Providing and laying of gabion structure from mechanically woven double twisted wire crates and mattresses of different sizes with diaphragm; made out of heavy-zinc coated dia 3 mm mesh-wire, 3.9 mm selvedge-wire, and 2.4 mm binding-wire woven to 100 mm x 120 mm hexagonal mesh; placing for all lifts including in water and at different batter; manually filling with boulders, weaving, all complete as per Drawings and as instructed by the Engineer. [Spec Cl no. 2402].	Cubic meter	6,182.68			
29	4.7	DOR 2510(4)	12.5mm thick cement sand plaster in (1:4) ratio on wall with good finish including supplying of approved quality of cement & sand, racking the joint, Chipping the concrete surface, wetting of surfaces & curing the work all complete as per the design, drawing and specification.. [Spec Cl no. 2510,(4)].	Square meter	1,300.76			
			Sub-total of Masonry and Gabion Works					
	5.0		Plain and Reinforced Cement Concrete Works					
30	5.1		Providing and placing cement concrete for all lifts and necessary formwork, including in water and at different batter, as per Drawings, or as instructed by the Engineer; with mechanical mixing, use of approved admixtures, compaction, and curing all complete for the following concrete grades: [Spec Cl no. 2000].					



S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
	a	DOR-2000	M 10/40	Cubic meter	526.30			
	b	DOR-2000	M 15/20	Cubic meter	2,968.26			
	c	DOR-2000	M 25/20	Cubic meter	5,219.37			
	d	DOR-2000	M 30/20	Cubic meter	490.50			
31	5.2	DOR-2014,2018 , 2019	Providing different diameters of Fe 500 High Yielding Strength Deformed Steel reinforcement in Reinforcement Cement Concrete for all lifts; including, laying, cutting, bending, placing and binding as well as including chairs, concrete spacers and binding wire; as per Drawings or as instructed by the Engineer [Spec Cl no. - 2014,2018, 2019].	Metric Ton	542.15			
32	5.5	SS DOR 1402	Providing and laying of precast / cast in situ 50 mm thick cement concrete slab footpath on 12 mm thick 1: 3 cement sand mortar over the prepared base, all complete as per Drawing and Technical Specifications. [SS 1402].	Square meter	1,601.25			
33	5.6	SS DOR 1401	Providing and laying of M20 precast cement concrete Kerb 38 cm * 20 cm * 25 cm (H*B*L) with 12 mm thick 1:3 cement sand mortar bedding and joints including foundation excavation levelling but excluding foundation concrete for foundation or sand gravel material, all complete as per Drawing and Technical Specifications [Spec Cl no. 1401].	meter	1,067.50			
			Sub-total of Plain and Reinforced Cement Concrete					

S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
	6.0		Hume-Pipe Works					-
34	6.1		Providing and laying Reinforced Cement Concrete collar-jointed pipe of Grade NP3 of following diameters for culverts including fixing with 7.5 N/sq.mm strength cement-sand mortar as specified in the Special Specifications, Drawings, or as instructed by the Engineer: [Spec Cl no.625, 701].					
	c	DOR-625, 701	900 mm	meter	150.00			
			Sub-total of Hume-pipe Works					
	7.0		Bio-engineering Works					
35	7.3	DoR-2800	Providing and laying of turf by providing about 50 mm thick fine grass squares, dressing of slope, light mulching and watering, laying of grass squares, anchoring by live pegs, as per Drawings or as instructed by the Engineer, and light tamping [Spec Cl no. 2800].	Square meter	34,550.00			
36	7.7	DoR-2800	Providing and planting of rooted grass slips on slopes <45o including preparation of grass slips, preparing rows of 50 mm deep planting holes at spacing of 100 mm in row and 250 mm spacing between two rows, inserting grass slips into the holes as per Drawings or as instructed by the Engineer, backfilling the holes and watering. [Spec Cl no. 2800].	Square meter	3,600.00			
37	7.8	DoR-2800	Providing and laying of brush-layers made out of 600 mm long up to dia 40 mm live cuttings, including trimming of hill slope, 400 mm deep trenching, providing mulch cushion, laying of live cuttings to form brush layer as per Drawings or as instructed by the Engineer, backfilling, hand compaction and watering. [Spec Cl no. 2800].	meter	600.00			

S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
38	7.15	DoR-2800	Planting of Trees and their Maintenance for one Year, Providing and Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year [Spec Cl no. 2800].	Number	800.00			
39	7.16	DoR-2800	Providing and fixing MS iron tree guard 60 cm dia and 2 meter high above ground level formed of 4 Nos (25 x 6mm) and 8 Nos (25 x 3 mm) vertical MS riveted to 3 Nos (25 x 6 mm) iron rings in two halves, bolted together with 8 mm dia and 30 mm long bolts including painting two coats with paint of approved brand over a coat of priming, complete in all respects. [Spec Cl no. 2800].	Number	800.00			
			Sub-total of Bio-engineering Works					
	8.0		Road Safety and Traffic Management Work					
40	8.1	1501	Providing and installation of non-reflective warning (750 mm high triangular or 400 mm x 400 mm rectangle), mandatory (dia 600 mm) and informatory (600 mm x 400 mm) signs, made out of 2 mm thick MS sheet with back support frame fixed on medium 50 mm GI tube firmly fixed to the ground through 300 mm x 300 mm x 300 mm M10/40 grade cement concrete, as per Drawings or as instructed by the Engineer. [Spec Cl no. 1501].	Number	256.00			
41	8.2	1501	Providing and installation of non-reflective 1.8 m x 1.2 m Project Information Board, made out of 2 mm thick MS sheet with back support frame fixed on medium 75 mm GI tube firmly fixed to the ground through 300 mm x 300 mm x 500 mm M10/40 grade cement concrete, as per Drawings or as instructed by the Engineer. [Spec Cl no.1501].	Number	2.00			

S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
42	8.3	1504	Providing and laying of hot applied thermoplastic compound in thickness ≥ 2 mm with reflectorizing glass beads to draw white or yellow road markings in patterns as per Drawings or as instructed by the Engineer on new road surface [Spec Cl no. 1504].	Square meter	3,966.11			
43	8.4	1501	Providing and applying 2 coats of enamel paint to create background and drawing of characters and patterns on masonry or concrete surface to create painted traffic signs, or information on GRM, as per Drawings or as instructed by the Engineer. [Spec Cl no. 1501].	Square meter	1,596.10			
44	8.5	1505	Providing and installation of retro-reflective 100 mm x 100 mm die-cast aluminum road studs, installation includes drilling hole and bolting and bedded in bituminous grout/ epoxy mortar, as per Drawings or as instructed by the Engineer. [Spec Cl no. 1505].	Number	2,699.00			
45	8.6	1507	Providing and installation of 1.5 m long, 150 mm x 150 mm RCC delineators made out of M15 concrete protruding 1 m above ground level, painted 200 mm wide strips alternatively in black and white enamel, as per Drawings or as instructed by the Engineer. [Spec Cl no. 1507].	Number	2,295.00			
46	8.7	1511	Provide and erect double "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail bolted to 150 mm x 75 mm x 5 mm IS MC series channel 2 m long vertical post using spacers of same section. The vertical post should be 1 m underground and at 2 m spacing. All steel parts to be galvanized by hot dip process, all complete as per drawings and as instructed by the Engineer. [Spec Cl no. 1511].	meter	1,120.00			
47	8.9	1506	Providing and installation of the following kilometer-post made out of M15 concrete, enamel painted with white background and black lettering, as per Drawings or as instructed by the Engineer: [Spec Cl no. 1506].					
	a		1-km marker	Number	12.00			

S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
	b		5-km marker	Number	5.00			
48	8.1	1300	Providing and making of Rumble strips with Asphalt Concrete, 15-20mm high at center, 250mm wide placed at 1m center to center at approved locations to control speed, marked with white strips of road marking paint all complete as per Drawings and Technical Specification [Spec Cl no. 1300].	Square meter	980.00			
			Sub-total of Road Safety and Traffic Management Works					
	9.0		Performance Based Maintenance Activities					
49	9.1		Provide and execute Performance Based Maintenance of the project road ensuring performance indicators defined in the Contract clauses are achieved for the following years starting from issuance of Construction Completion Certificate:: [Spec Cl no. 2910]:					
	a	DOR-2910	Year-1: on achievement of PBM indicators	km.mon th	194.71			
	b	DOR-2910	Year-2: on achievement of PBM indicators	km.mon th	194.71			
	c	DOR-2910	Year-3: on achievement of PBM indicators	km.mon th	194.71			
	d	DOR-2910	Year-4: on achievement of PBM indicators	km.mon th	194.71			
	e	DOR-2910	Year-5: on achievement of PBM indicators	km.mon th	194.71			
	f	DOR-2910	Emergency fund for PBM Works and Services	Provisio nal Sum	1.00	5,000,000.00	Fifty Lakh	5,000,000. 00
			Sub-total to Performance Based Maintenance Activities					

S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
	10.0		ESMP Guided Activities					-
50	10.1	ESMP, SP 111 (6)	Providing and ensuring continuous use of reflective jacket and helmet by all workers and visitors at site as well as additionally additional appropriate Personnel Protective Equipment (reflective clothe, helmet, boots, gloves, ear plug, harness, etc. as instructed by the Engineer) by workers requiring them as per the nature of tasks. [ESMP, SP 111 (6)].	month	24.00			
51	10.2	SP 111 (7) and ESMP	Providing and maintaining first aid box (containing general essential medicine, gauze, roll bandage, cotton, scissors, antiseptic solution, alcohol wipes, thermometer, etc.) at all active heavy equipment and at worker camps, paste conspicuous notice boards directing where these are situated [SP 111 (7) and ESMP].	month	24.00			
52	10.3	ESMP	Providing and maintaining sturdy barricades, fences and caution signs as per Drawings or as instructed by the Engineer, at all active sites [ESMP].	month	24.00			
53	10.5	DOR 111(3) (4) and (5) and ESMP	Providing safe, secure and hygienic and gender segregated worker camps following PLRIP labour Camp Guideline -2026 with adequate number of ventilated rooms/ beds, toilets, water for washing/ bathing, kitchen (with washbasin, dish cleaning facilities, LPG/ electric stoves), garbage bins. Illustrious posters in local language on code of conduct for workers, occupational health, awareness on infectious diseases, location of first-aid kits, location and call number of nearest health facility should be pasted in the common area of the camps. [SS 111 (3), (4), (5) and ESMP].	month	24.00			
54	10.6	DOR 111 and ESMP	Controlling air pollution through water sprinkling as instructed by the Engineer. [SS 111 and ESMP].	km.mon th	486.78			
55	10.8	DOR 111 (15) and ESMP	Reinstatement of worker camps, quarries, crusher plants, bitumen storage and stock pile sites as well as to the original stage as well as clearing of the roadway and drains at the completion of works as instructed by the Engineer. [SS 111 (15) and ESMP].	lumpsu m	1.00			

S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
56	10.9	ESMP, SP 1514	Construction of Bus Shelter at various location with PWDs friendly design feature along the alignment as per Provided Standard Drawing and Specification all complete [ESMP].	lumpsum	8.00			
57	10.11	ESMP, SP 111 (11), (12) (13)	Carryout Environmental Monitoring for Air, Noise and Water Quality {ESMP, SP 111 (11), (12) (13)}	Provisional Sum	1.00	385,000.00	Three lakh Eighty-Five Thousand	385,000.00
			Sub-Total of ESMP Guided Activities					
	11.0		Dayworks					-
58	11.1		Supply of workers					
	a		skilled workers (masons, carpenters, blacksmiths, surveyors, etc.)	person.day	50.00			
	b		unskilled workers	person.day	200.00			
59	11.2		Supply of material					
	a		Cement	Kilogram	500.00			
	b		Sand	Cubic meter	5.00			
	g		concrete aggregate	Cubic meter	10.00			
	h		Supplying and laying Reinforced Cement Concrete collar-jointed pipe of Grade NP3 as instructed by the Engineer:					
			300 mm	meter	40.00			
			600 mm	meter	40.00			
60	11.3		Supply of equipment with fuel and operators					
	a		dump-truck of 4.6 cum capacity	hour	50.00			

S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
	b		tractor	hour	50.00			
	c		backhoe	hour	20.00			
	d		water pump	hour	50.00			
	e		excavator	hour	20.00			
61	11.4		Supply of excavator for maintenance of road or else as required and instructed by engineer including operator and other charges	hour	50.00			
			Sub-total to Dayworks					
	12.0		General Works					
62	12.1	DOR-100 GCC 19	Purchasing and maintaining insurance cover for works, plants, materials, workers, and third party to the extent required by the contract clauses [Spec Cl no.100, GCC 19].	lumpsum	1.00			
63	12.2	DOR-504	Establish and maintain a site laboratory with equipment, accessories, personnel and consumables for testing of concrete, zinc cover of wire, sand, aggregates, and all standard tests required as per Specifications. [Spec Cl no. 504].	month	24.00			
64	12.3	DOR-504, 510	Sampling, transporting and testing of construction material for additional tests then specified in the Specifications at an accepted nearest material testing laboratory as instructed and agreed by the Engineer. [Spec Cl no. 504, 510].	Provisional Sum	1.00	300,000.00	Three Lakh	300,000.00
65	12.4	DOR-109	Provide and perform regular maintenance of the existing road to keep the road serviceable through out the construction period as per specification and instruction of the Engineer [Spec Cl no. 109].	km.month	389.42			
66	12.5	DoR-105	Relocation of services and minor infrastructures i.e electric pole, cables, chautara, chautara, irrigation canal, pipes and other EMP-warranted activities, as instructed by the Engineer [Spec Cl no. 105].	Provisional Sum	1.00	11,100,000.00	Eleven million one hundred thousand	11,100,000.00



S.N	Pay Item No.	Specifications Reference	Item Description	Unit	Quantity	Unit Rate in Figures (NPR)	Unit Rate in Words (NPR)	Amount (NPR)
67	12.6	DOR 116	Provide color photographs and video of the construction works before, during and after construction as per specification and as directed by the Engineer [Spec Cl no. 116]	month	24.00			
68	12.7	GCC 21.1	Provision for Dispute Avoidance and Adjudication Board (DAAB) (Employer Portion)	Provisional Sum	1.00	1,200,000.00	Twelve Lakh	1,200,000.00
			Sub-total to General Works					
			Total (Base Cost)					
			Total Provisional Sum					
			Base Cost without PS					
			VAT @13% of Base Cost					
			Total Cost including VAT & PS					