



# बी.पी. कोइराला मेमोरियल क्यान्सर अस्पताल भरतपुर, चितवन

दररेट (Quotation) पेश गर्ने सम्बन्धी सुचना  
सुचना प्राकशित मिति २०८२/१२/१२

यस बी.पी. कोइराला मेमोरियल क्यान्सर अस्पतालमा **Construction of Tissue Disposal Plant** को निर्माण कार्य सोझै खरिद गर्नुपर्ने भएको हुँदा उक्त सम्बन्धि कार्य गर्ने कम्पनी/फर्मले यस सुचना प्रकाशित भएको मितिले ५ (पाँच) दिनभित्र यस अस्पतालमा आफ्नो तपसिल बमोजिमका कागजातहरू संलग्न गरि सो निर्माण कार्यको प्रचलित बजार भाँउ अनुसारको दररेट प्रस्ताव यो सूचना प्रकाशित भएको मितिले ५ (पाँच) दिनमा (अर्थात् मिति २०८२/१२/१७ गते दिउँसो ०४:३० बजेभित्र) यस कार्यालयमा आइपुग्ने गरी सोझै दर्ता गर्नुहुन यो सुचना प्रकाशित गरिएको छ । थप जानकारीको लागि अस्पतालमा सम्पर्क गर्न सकिने छ । तोकिएको मिति भन्दा पछि पेश भएको दररेट मान्य हुने छैन ।

## संलग्न गर्नुपर्ने आवश्यक कागजात

- आ.व. २०८२-०८३ को लागि मौजुदा सुचि दर्ताको लागि निवेदन (अस्पतालको मौजुदा सुचिमा दर्ता नभएका फर्म/कम्पनिको लागि मात्र)
- मु.अ.कर दर्ताको प्रमाणपत्र
- फर्म/कम्पनि दर्ताको प्रमाणपत्र नविकरण समेत
- निर्माण व्यवसाय सम्बन्धी इजाजतपत्र
- आ.व. २०८१/०८२ को करचुक्ता प्रमाणपत्र वा आय विवरण पेश गरेको प्रमाण
- दररेट पेश गरेको निवेदन (यसैसाथ संलग्न बमोजिम)

नोट: काम सम्पन्न गर्नुपर्ने अवधी कार्यादेशको मितिले १५ दिन

कार्यकारी निर्देशक

मिति: २०८२/१२/

श्रीमान् कार्यकारी निर्देशकज्यू,  
बी.पी. कोइराला मेमोरियल क्यान्सर अस्पताल,  
भरतपुर चितवन ।

**विषय : दररेट पेश गरिएको सम्बन्धमा ।**

प्रस्तुत विषयमा तँहा अस्पतालबाट Construction of Tissue Disposal Plant को निर्माण कार्यको लागि माग गरेको दररेटमा देहाय बमोजिमको दररेट प्रस्ताव गरेको व्यहोरा अनुरोध छ ।

तपसिल

S. No.	Description of Item	Quantity	Unit	Per Unit rate in Fig (NPR- Without VAT)	Per Unit Price in Word	Total Amount
1	Earthwork excavation in foundation and trenches in all type of soil excluding rock in both dry and wet condition including shoring and strutting when ever necessary. Also pumping out water as when necessary from the trenches etc. having lead of 30 m as per drawings, specifications and instructions of site Engineers all complete.	694.50	Cft			
2	Earthwork in filling in foundation, under floors and other structures in layers not exceeding 15 cm.including adequate watering, ramming and consolidation (having ofcompaction more than 95% relative dry density) with excavated soil obtained from the site as per drawings, specificaitions and instructions of site Engineers all complete.	293.13	Cft			
3	Supplying and laying dry brick flat soling with first class chimney made bricks with filling sand in the joint as per instruction, specification and drawing all materials and labour complete	230.24	Sft			
4	Supplying and placing Plain Cement Concrete for RCC in ratio 1:2:4 as specified machine mixed and mechanically vibrated at all depth and heights below and above plinth level including curing all material and labour complete as per instruction	86.36	Cft			
5	Providing and laying chimney made first class Brick work in cement sand mortar 1:4 (1 cement: 4 coarse sand) with in specified places in all heights and level including the cost of single or multi stage scaffolding, curing, raking joints, provision for recesses, openings, toothing etc. as per instructions all complete.	81.00	Cft			
6	Providing and laying of approved brand and color Vitrified Homogeneous non-slippery tile of size (610mm x 610 mm) on floor and wall of Cabin and ward in cement sand mortar base (1:2) in given line and level over screeding including filling the joint by non-shrunk tile grout, necessary plaster works as per instructions all complete.	261.00	Sft			

S. No.	Description of Item	Quantity	Unit	Per Unit rate in Fig (NPR- Without VAT)	Per Unit Price in Word	Total Amount
7	Supply and fitting of 3000 liters extra heavy hiltake tank in the trench pit including necessary cutting, levelling etc as per instructions all complete.	1.00	Set			
8	Supply and fitting of 2" Dia. 20 Rft CPVC pipes including necessary fittings such as ball valve, CPVC Union, CPVC female brass adaptor, CPVC Tank Adaptor, Coupling, CPVC Solvent cement etc cutting, levelling as per instructions all complete.	20.00	Rft			
9	Supply and fitting of 3" Dia heavy Class MS pipe Hulas or equivalent including necessary cutting, fabrication, welding Enamel painting etc as per instructions all complete.	165.00	Kgs			
10	Supply, fabrication, welding and fitting of SS Basket of size 2'-6" x 2'-6" x 3'-0" (3/4" x 3/4" Mesh making with 6mm SS rod) including necessary cutting, levelling etc as per instructions all complete.	1.00	Set			
11	Supply, fabrication, welding and fitting of SS Frame with (openable cover lid of size 3'-0" X 3'-0" with cap) including necessary cutting, levelling etc as per instructions all complete.	1.00	Set			
<b>Total Amount (Without VAT)</b>						

नोट: काम सम्पन्न गर्नुपर्ने अवधी कार्यादेशको मितिले १५ दिन

- क. त्यस अस्पतालको कोटेशन पेश गरेको मालसामान/उपकरण आवश्यक निर्माण तथा सेवा सम्बन्धमा कार्यादेश /खरिद आदेश पश्चात तोकिएको समयमा आपूर्तिको व्यवस्था मिलाई बिल भर्पाई समयमा नै बुझाउने छु ।
- ख. सार्वजनिक खरिद कारवाहीमा भाग लिन रोक लगाइएको वा प्रचलित सार्वजनिक खरिद कानून बमोजिम कालो सुचिमा परी अयोग्य भएको छैन साथै प्रस्तावित हुने खरिद कारवाहीमा कुनै किसिमबाट स्वार्थ बाझिने अवस्था सिर्जना हुने छैन ।
- ग. पेश गरेको दररेट प्रचलित बँजारभाउ अनुसारको छ र यदि उक्त दर प्रचलित बँजारभाउ अनुसारको नपाइएमा त्यसको जिम्मेवारी हामी लिनेछौं भनी स्वीकार गर्दछौं । म/हामी संलग्न फर्म वा कम्पनिबाट पेश भएका कागजाहरु तथा गरेका कार्यहरु गलत वा झुटा ठहरीए कानून बमोजिम सहुँला बुझाउला ।

फर्म/ कम्पनीको नामर ठेगाना		अख्तियार प्राप्त व्यक्तीको नाम:	
		आधिकारीक दस्तखत:	
छाप			
स्था. ले.नम्बर (PAN NO)		मोबाइल नं /फोन नं:	