

Government Sudur Paschim Province
Ministry of Physical Infrastructure Development
Dhangadhi, Kailali, Nepal

BILL OF QUANTITY (BOQ)

Handwritten signature
9/17

Name of Project : Aluminium Partation, Office Cabinet and Office Wall rack work of Mopid

Location : Dhangadhi, Kailali

Contract ID: MoPID-SP/DP/Works/01/082-83

Name of Work : Aluminium Partation, Office Cabinet and Office Wall rack work .

S.No.	Description of Items	Unit	Total Quantity	Rate (NRs.)		Remark
				In Figures	In Words	
A. CIVIL WORKS:-						
1	Site preparation, Dismental brick wall for door and starting the construction work and clearing the site all complete after completion of the work as per the instruction of site incharge.	Job	1.00			
2	Construction of Office Wall rack (DEPTH=1'- 2" HEIGHT=6'-7") All construction made out of 18mm thick double coated A-grade commercial ply structure and 1mm thk formica finished on top, sides and all exposed surfaces including handle, Hydraulic Hinges , screws, favicol and other necessary accesories as per approved design and instruction by site architect all complete.	Sqm	6.00			
3	Construction of Office Cabinet (DEPTH=1'- 2" HEIGHT=10'-6") All construction made out of 18mm thick double coated A-grade commercial ply structure and 1mm thk formica finished on top, sides and all exposed surfaces including handle, Hydraulic Hinges , screws, favicol and other necessary accesories as per approved design and instruction by site architect all complete.	Sqm	16.80			
4	Aluminium Partation – Fabrication, Supplying & Fixing of 100mm Series in Natural wooden Color anodized with necessary hardware, 5mm Al. Composite / 5mm Clear Glass / 8mm Nepal Board, Section Size 101.6x44.5x1.0mm	Sqm	37.23			
5	UPVC Single Door (white colour with 5mm glass) with all complete as per the approval of the site engineer.	Sqm	2.05			
	Total					
	Value Added Tax(VAT) @ 13%					
	Grand Total					

Total in Words:

Signature:-

Name of Firm:-

Address:-

Date:-

Stamp:-